


Successful Foundation Preparations in Karst Bedrock of the Masonry Section of Wolf Creek Dam

David M. Robison, P.G.


Geotechnical and Dam Safety Section,
Louisville District, U.S. Army Corps of Engineers




US Army Corps of Engineers
BUILDING STRONG®



Wolf Creek Dam Project Features




Wolf Creek Dam Location and Purpose



- Location: Cumberland River in Russell County, Kentucky
- Authorized Purposes: Flood Control and Hydropower
- Additional Benefits: Navigation, Recreation, Water Supply, and Water Quality
- Reservoir first impounded in December 1950




Karstic Foundation



Karstic Foundation



Dam and Foundation Profile




BUILDING STRONG®

Masonry/Concrete Dam Upstream Profile

37 Monoliths

10 Tainter gates
37' x 50' each

Embankment
wrap-around



Stair-step
foundation


6 sluice gates
4' x 6' each

6 power intakes
to turbines




BUILDING STRONG®

Exploratory Grouting (2011-2012)




Dam Site Before Construction




OLUF CREEK DAM.--View of dam site from left bank, downstream from axis of dam. 18 June 1941.

22,256


Preliminary Borehole Exploration (1930's) – 200 ft. centers




Additional Early Borehole Exploration




Bedrock Surface Contours



Preliminary Borehole Exploration (1940)



Early Borehole Exploration



BUILDING STRONG®

Overburden Removal



Mon. No. 20 Removal of Overburden by Dredge
Photo No. 114



Mon. No. 20 Removal of Overburden by Dredge
Photo No. 137




Mon. No. 20 Final Removal of Overburden by Shovel
Photo No. 159 after Dredging Operation



Q2-61/29 Masonry Menolith 37-32 1+00.8

Overburden Removal



MON. No 29
PHOTO No 153

REMOVAL OF OVERBURDEN
BY SHOVEL

Additional Drilling Post-Overburden Removal

Before rock removal was begun in an area, a study was made of all geological information pertinent to that area. This geological information consisted of the logs of the holes drilled during the preliminary investigations of the site as well as the various informative reports prepared by the Geological Section. From this information, it was usually possible to determine within reasonable accuracy the quantity and depth of rock to be removed in a given area to provide structurally sound foundations.

As the preliminary investigation drillings were made on one hundred (100) foot centers, it was decided that if a closer on-center pattern of drilling was made, a better knowledge of rock conditions would be afforded and rock removal would be confined to a minimum.



BUILDING STRONG®

Additional Drilling Post-Overburden Removal


Beginning at the axis, two (2) inch percussion drilled holes were drilled on twenty (20) foot centers normal to and paralleling the axis until the entire area of the monolith or other structure had been drilled. These holes were drilled vertically, and were sixteen (16) feet deep. The drilling was carefully observed in order to locate possible subsurface solution channels, soft bedding of appreciable thickness, or other defects. A log was prepared of the results of the test drilling, and compared with the original geological findings. Upon completion of this review, the removal of the necessary rock was ordered.



BUILDING STRONG®

Blasting






Monolith # 30 Rock Removal by Shovel Elev. 662
PHOTO N° 52

Manual Removal of all Rock not “Firmly Bedded”



Rock Removal



Bedrock Excavation Monoliths 37-30



Bedrock Excavation Monoliths 37-30



Mon.No.32
Cleaning Out Solution Channel

Photo No.89

Bedrock Excavation Monoliths 37-30



Mon.No.32

Photo No. 139


Widening & Exploring Solution Channel



ONG®

Large Solution Channel Excavated

Looking Downstream Mon. 37



Second Channel with First



Solution Channel Cleaning



Solution Channel Cleaning



Bedrock Excavation Monoliths 29-25

Wolf Creek Dam, 23 April 1947. General
view Masonry Area from Tower. Q2-61/358

Bench
Elev. 555


Bench
Elev. 558

22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37



BUILDING STRONG®

Contact Grouting




Bedrock Excavation Monoliths 24-19

(Power Intake Section)



Bedrock Excavation Monoliths 29-19


(Power Intake Section)



Monolith 20 –Grouting without Pressure



Bedrock Excavation Monoliths 18-14



Bucket Excavation Monoliths 18-14

(Spillway Section)

PRELIMINARY EXPLORATION:

During the rock removal a solution channel was uncovered that extended along the entire downstream toe of the bucket. It was excavated to its full depth, and after its removal, percussion drilled holes on 10-foot centers were drilled 6 to 10 feet deep, into the area it occupied, and revealed the rock to be sound.



BUILDING STRONG®

Bucket Excavation Monoliths 18-14

(Spillway Section)



BUILDING STRONG®


Bedrock Excavation Monoliths 13-9

(Spillway Section – River Channel)



Bedrock Excavation Monoliths 8-1

(Left Abutment)




Bedrock Excavation Monoliths 8-1

(Left Abutment)



Mon. #6 Initial Pour. Form on Mons. 6-7 Joint.



Bedrock Excavation Monoliths 8-1 (Left Abutment)




BUILDING STRONG®

Contact Grout System Along Mons. 5-6 Joint.

Left Abutment


Downstream



Grout Holes and Drains



BUILDING STRONG®





Grout Holes and Drains



BUILDING STRONG®

Masonry/Concrete Dam Foundation Profile



Original Dam Construction Cost

TOTAL CONTRACT COST	\$ 19,648,450.36
DEDUCTIONS:	
The amount due the Government for Utilities and for credit assumed from S. A. Healy, Inc., the original contractor. In accordance with paragraph (f) of Article 29 of Contract No. W-40-058-eng-249	- \$ 952,351.26
The amount equals to the number of yards of concrete placed multiplied by \$0.40 for a given length of time. In accordance with paragraph (d) of Article 29 of Contract No. W-40-058-eng-249.	- 447,889.51
Payment for Government furnished cement used by contractor in erecting construction plants and facilities. In accordance with paragraph 1-C-10(b)(3) of the Specifications.	- 102,187.82
Deduction in accordance with Modification Number 6 dated 9 December 1946.	- 18,452.38
Deduction in accordance with Modification Number 15 dated 8 September 1947.	- <u>5,361.67</u>
NET PAID CONTRACTOR	\$ 18,122,207.72

Original construction cost about **\$240 million** in 2015 dollars

Recent remediations of embankment cost about **\$600 million**



BUILDING STRONG®


Embankment Cross Section

Impervious Rolled Fill

Homogenous, well compacted, low plasticity clay.

Drainage Blanket

Choked with fines, difficult to distinguish from the alluvium in recent borings



Cutoff Trench

Compaction was likely variable. Placement and compaction, often by hand, occurred against rough vertical walls and under rock overhangs.

Alluvium

Predominately fine grained but with sand and gravel lenses

Cutoff Trench Design Philosophy (Core Trench Foundation Report, 1943):

“Overhangs and loose rock will be removed only where they cross the lines of the trench, since the earthfill in the sides of the trench will have the function only of stability and not of an absolutely uniform tight contact with the trench walls.”




Placement and Compaction of Cutoff Trench Fill



Distress Indicators Observed in the 1960's

At the time, there were no instruments to monitor the project.



Turbid Discharge into the Tailrace in 1967




Sinkhole Observed near Switchyard in 1968



Sinkhole Observed near Switchyard in 1968





Plan Legend

	Roadway		1967 Muddy Flow
	ICOS Walls		1968 Sinkholes
	Barrier Wall		New Grout Lines
	1960s Grout Lines		2011-12 Switchyard Grout Lines


Top of Rock Contours - Elevation (ft)

<520	540-550	570-580
520-530	550-560	580-590
530-540	560-570	590-600
		600-800




BUILDING STRONG®

Emergency Grouting



1975 ICOS Combination Wall



Wet Areas
(shown in blue)

ICOS Diaphragm Wall

Since 1990 the extent of the wet areas has steadily increased, reaching the maximum extent in March of 2004.

Legend

0 250 500 1,000 Feet


N

March 09, 2010




03.09.2010

Persistent Wet Areas



ACT Grouting (2007-2008)


*1300 holes
900,000 gallons of grout
\$70 million
Completed September 2008*



Barrier Wall Construction (2009-2013)



Barrier Wall Construction (2009-2013)



Questions?



BUILDING STRONG®